



**AMERICAN FORK - ART DYE PARK (NORTH SITE-BALL FIELDS)  
 BID SCHEDULE FOR MARCH 21, 2019**

ITEM NO.	ITEM DESCRIPTION	QTY.	UNIT	UNIT PRICE	TOTAL
<b>MOBILIZATION &amp; SITE EXCAVATION</b>					
1	MOBILIZATION / DEMOBILIZATION	1	LUMP		
2	CLEAR/GRUBB/CUT & FILL/ADJUST IRR. VALVES (INCLUDE STOCKPILE, SCREENING & REUSE OF SOIL)	1	LUMP		
3	CONSTRUCTION MANAGEMENT AND MATERIALS TESTING & INSPECTION	1	LUMP		
4	EROSION CONTROL & SWPPP (CONTRACTOR TO PROVIDE FINAL PLAN, NOI, AND INSPECTIONS)	1	LUMP		
5	COMPACTED IMPORT GRANULAR FILL FOR PIPE TRENCHES (UTILITIES: WATER, SEWER, STORM)	90	CUBIC YARD		
SUB TOTAL					\$ -

<b>WEST SIDE CURB &amp; GUTTER AND EXISTING SOUTH/SOUTHEAST PARKING IMPROVEMENTS</b>					
6	24" CURB (INCLUDES 6" UNTREATED BASE COURSE (UTBC) & NEW ISLANDS IN EXISTING PARKING)	862	LINEAR FOOT		
7	ADA RAMPS	2	EACH		
8	REMOVE EXISTING CONCRETE SIDEWALK (WEST SIDE PLAZA CELL TOWER ENTRANCE )	1,240	SQUARE FOOT		
9	SAW-CUT AND REMOVE EXISTING ASPHALT (SOUTH/SOUTHEAST PARKING AREA)	2,140	SQUARE FOOT		
10	PARKING STALL STRIPING (NEW ADA STALLS ONLY- EXISTING PARKING)	1	LUMP		
11	12" STOP BAR & CROSSWALK STRIPING (NEW INTERSECTIONS - EXISTING PARKING AREA)	40	LINEAR FOOT		
12	<b>PARKING AND ROADWAY SIGNAGE</b>	32	EACH		
SUB TOTAL					\$ -

<b>SITE UTILITIES</b>					
13	CULINARY WATER - PROVIDE STUB TO RECONNECT EXISTING WATER TO FUTURE BUILDING (6" PVC-SDR35 W/ FITTINGS) - COORDINATE WITH BUILDING CONTRACTOR	1	LUMP		
14	6" WATER SERVICE LATERAL (BLUE BRUTE, VALVE & FITTINGS)	546	LINEAR FOOT		
15	2" WATER SERVICE LATERAL (BLUE CTS POLY & FITTINGS)	160	LINEAR FOOT		
16	2" WATER SERVICE METER & VAULT W/ STOP & WASTE & FITTINGS	1	EACH		
17	FIRE HYDRANT ASSEMBLY (INCLUDES 6" PVC WATERLINE) - KEEP PARTS AND PROVIDE TO CITY	1	EACH		
18	SANITARY SEWER - PROVIDE STUB TO RECONNECT EXISTING SANITARY SEWER TO FUTURE BUILDING (8" PVC-SDR35 W/ FITTINGS) - COORDINATE WITH BUILDING CONTRACTOR	1	LUMP		
19	6" SANITARY SEWER CLEANOUT	1	EACH		
20	STORM DRAIN CATCH BASINS	12	EACH		
21	48" STORM DRAIN MANHOLES	4	EACH		
22	STORM DRAIN CLEANOUTS (ROOF DRAINS)	4	EACH		
23	8" STORM SEWER ADS	520	LINEAR FOOT		
24	15" STORM SEWER ADS	1,320	LINEAR FOOT		
25	18" STORM SEWER ADS	235	LINEAR FOOT		
26	24" STORM SEWER ADS	350	LINEAR FOOT		
27	STORMWATER TREATMENT (TRASH GUARD, CONCRETE END SECTION, RIP RAP)	1	LUMP		
28	<b>ELECTRICAL (PANELS, EQUIPMENT, ALL CONDUIT &amp; WIRE, STUB UP'S TO NEW BUILDING)</b>	1	LUMP		
29	<b>INSTALL MUSCO LED LIGHTING SYSTEM FOR PARKING, PLAZA, AND SIDEWALKS (COMBINE W/ SPORTS LIGHTING INSTALL AS LUMP SUM (SEE ITEM 30))</b>				
SUB TOTAL					\$ -

<b>BALL FIELDS (3-EXISTING UPGRADED FIELDS, 1-NEW 300' FIELD, AND 1-NEW 260' FIELD)</b>					
30	<b>INSTALL MUSCO LED SPORTS FIELD LIGHTING SYSTEM (INCLUDES ALL WIRE &amp; CONDUIT)</b>	1	LUMP		
31	<b>SHADE SAIL 8' X 20' X 8'</b>	10	EACH		
32	<b>SHADE SAIL 14' X 25' X 8'</b>	10	EACH		
33	<b>ALUMINUM 15' DUGOUT BENCH WITH BACK</b>	10	EACH		
34	<b>ALUMINIUM BLEACHERS</b>	10	EACH		
35	<b>SCOREBOARD</b>	5	EACH		
36	<b>BASES/LINE EQUIPMENT/FOUL BARS</b>	3	LUMP		
37	BALL FIELD SIGNAGE (IDENTIFY FIELDS BY INDIVIDUAL FIELD NUMBERS 1 THROUGH 5)	5	EACH		
38	REINFORCED CONCRETE MOW STRIP (16" WIDE - UNDER ALL NEW PERIMETER FENCING)	2,200	SQUARE FOOT		
39	BASEBALL INFIELD MIX (24,600 FT <sup>2</sup> @ 4 INCH DEPTH) REPLACE ALL 5- FIELDS)	285	CUBIC YARD		
40	22' GALVANIZED BACKSTOPS WITH 45° TOP CANTILEAVER	2	EACH		
41	6' GALVANIZED CHAINLINK PERIMETER BALLFIELD FENCE (SIDE FIELD FENCING)	450	LINEAR FOOT		
42	12' GALVANIZED CHAINLINK PERIMETER FENCE (OUTFIELD FENCING FOR 3 SOUTH FIELDS ONLY)	1,450	LINEAR FOOT		
43	4" PERFORATED FLEX-DRAIN PIPE (ALONG OUTFIELD PERIMETER FENCING ONLY)	690	LINEAR FOOT		
SUB TOTAL					\$ -

<b>PARK &amp; PLAZA HARDSCAPE</b>					
44	CONSTRUCTION SURVEY	1	LUMP		
45	CONCRETE (5" DEPTH) PLAZA AREA/ SIDEWALK / DUGOUT	51,000	SQUARE FOOT		
46	UNTREATED BASE COURSE (UTBC) (6" DEPTH OVER 51,000 FT <sup>2</sup> ) PLAZA, SIDEWALK & DUGOUTS	1,780	TON		
47	14' WIDE (6" DEPTH) REINFORCED CONCRETE W/ UNTREATED BASE COURSE - FIRELANE	3,950	SQUARE FOOT		
48	14' WIDE (6" DEPTH) REINFORCED CONCRETE W/ UNTREATED BASE COURSE - CELL TOWER	3,380	SQUARE FOOT		
49	CAST IN PLACE RAISED CONCRETE PLANTERS	5	EACH		
50	4" X 6" CONCRETE LANDSCAPE MOW CURB	600	LINEAR FOOT		
51	INTERNAL DIRECTIONAL SIGNAGE	6	EACH		
52	RETRACTABLE BOLLARDS	7	EACH		
53	<b>BIKE RACKS</b>	3	EACH		
54	<b>TABLES &amp; CHAIRS (COVERED PLAZA AREA)</b>	10	EACH		
55	<b>TRASH RECEPTACLES</b>	12	EACH		
SUB TOTAL					\$ -

<b>PARK, PLAZA, AND BALL FIELDS LANDSCAPE</b>					
56	TOP SOIL FOR PLANTER BEDS (3,642 FT <sup>2</sup> @ 6" DEPTH)	68	CUBIC YARD		
57	TOP SOIL FOR TURF SOD AREAS (188,856FT <sup>2</sup> @ 4" DEPTH)	2,308	CUBIC YARD		
58	TURF SOD	188,856	SQUARE FOOT		
59	WEED BARRIER FABRIC	3,642	SQUARE FOOT		
60	SHREDDED BARK MULCH (3,645 FT <sup>2</sup> @ 4" DEPTH - PLANTER BEDS)	45	CUBIC YARD		
61	2" CALIPER TREE (EXACT PLACEMENT TO BE COORDINATED WITH CITY PM)	73	EACH		
62	5 GALLON SHRUB	97	EACH		
63	1 GALLON SHRUB	188	EACH		
64	IRRIGATION FOR TURF AND PLANTER AREAS	192,498	SQUARE FOOT		
SUB TOTAL					\$ -

**NOTE:** The quantities within this Bid Schedule are provided as a convenience for the bidder to aid in the bidding process. It will be the responsibility of each bidder to verify all quantities and provide all prices respectively. If additional items are identified beyond what is provided within this bid schedule, the bidder shall provide information and pricing for the item or items as part of their bid. The items will be reviewed by PEC and approved by the City. Any approved items will be added as an addendum accordingly.

**BASE BID (NORTH SITE) TOTAL** \$ -

Purchased by City and Installed by Contractor

<b>ALTERNATE BID ITEM 1.0 - MUSCO LIGHTING (UTILIZE EXISTING CELL TOWERS (2) IN PLACE OF PROVIDING TWO (2) NEW LIGHT POLES &amp; BASES)</b>					
A.1.0	ADD MUSCO LIGHTING FIXTURES TO EXISTING CELL TOWERS ON EXISTING TWO NORTH FIELDS. (PROVIDE DIFFERENTIAL INSTALL PRICE UTILIZING CELL TOWERS, AND DEDUCT PRICE OF INSTALLING TWO NEW (2) POLES & BASES)	2	EACH		
SUB TOTAL					\$ -