

SOCCER FIELDS



**AMERICAN FORK - ART DYE PARK (SOUTH SITE-SOCCER FIELDS)  
 BID SCHEDULE FOR MARCH 21, 2019**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
<b>MOBILIZATION/DEMOBILIZATION &amp; SITE EXCAVATION</b>					
1	MOBILIZATION / DEMOBILIZATION	1	LUMP		
2	CLEAR/GRUBB/CUT & FILL (INCLUDE STOCKPILE, SCREENING & REUSE OF SOIL ON-SITE )	1	LUMP		
3	CONSTRUCTION MANAGEMENT & MATERIALS TESTING (PROVIDED BY CONTRACTOR)	1	LUMP		
4	EROSION CONTROL & SWPPP (CONTRACTOR TO PROVIDE FINAL PLAN, NOI, AND INSPECTIONS)	1	LUMP		
5	OVER EXCAVATE NEW PARKING AREAS 12"	1,720	CUBIC YARD		
6	COMPACTED IMPORTED FILL 12"	1,720	CUBIC YARD		
7	COMPACTED IMPORT GRANULAR FILL FOR PIPE TRENCHES (UTILITIES)	560	CUBIC YARD		
SUB TOTAL					\$ -

<b>PARKING LOTS (2) (127 STALLS)</b>					
8	SAW CUT & REMOVE 24" CURB & GUTTER ALONG 550 E. (NEW APPROACHES TO PARKING LOTS, SOUTH WEST SIDE SECTION OF 550 EAST, NORTH EAST CORNER & ADA RAMPS)	660	LINEAR FOOT		
9	24" CURB & GUTTER (INCLUDES 6" UNTREATED BASE COURSE)	2,550	LINEAR FOOT		
10	ADA RAMPS	6	EACH		
11	ASPHALT PAVING (52,535 FT <sup>2</sup> @ 3" DEPTH)	985	TON		
12	UNTREATED BASE COURSE (UTBC) (52,535 FT <sup>2</sup> @ 6" DEPTH)	1,839	TON		
13	SAW CUT & REMOVE EXISTING ASPHALT	1,750	SQUARE FOOT		
14	8" CONCRETE WATERWAY WITH 6" UTBC BASE	2	EACH		
15	PARKING STALL STRIPING (127 STALLS + 1 @ 18' LONG)	2,304	LINEAR FOOT		
16	12" STOP BAR STRIPING & CROSSWALK STRIPING (2 CROSSINGS)	176	LINEAR FOOT		
17	<b>PARKING AND ROADWAY SIGNAGE (PURCHASED BY CITY INSTALLED BY CONTRACTOR)</b>	10	EACH		
SUB TOTAL					\$ -

<b>SITE UTILITIES</b>					
18	STORM DRAIN CATCH BASINS	3	EACH		
19	48" STORM DRAIN MANHOLES	2	EACH		
20	15" STORM SEWER ADS	420	LINEAR FOOT		
21	24" STORM SEWER ADS	98	LINEAR FOOT		
22	STORMWATER TREATMENT (TRASH GUARD)	1	LUMP		
23	<b>LED LIGHTING - PARKING &amp; STREET (PURCHASED &amp; INSTALLED BY CITY) CONDUIT INSTALLED BY CONTRACTOR (SEE BID ITEM 24 BELOW)</b>				
24	1.5" RIGID PVC CONDUIT W/ DETECTABLE TAPE & PULL ROPE (BURIED AT A MIN. 24" DEPTH)	3,000	LINEAR FOOT		
SUB TOTAL					\$ -

<b>PARK HARDSCAPE</b>					
25	CONSTRUCTION SURVEY	1	LUMP		
26	CONCRETE SIDEWALK (5' WIDE)	9,495	SQUARE FOOT		
27	UNTREATED BASE COURSE (UBC)(6")	414	TON		
28	4" x 6" CONCRETE MOW CURB	50	LINEAR FEET		
29	INTERNAL DIRECTIONAL SIGNAGE	2	EACH		
SUB TOTAL					\$ -

<b>PARK LANDSCAPE / SOCCER FIELDS</b>					
30	TOP SOIL (389,500 FT <sup>2</sup> @ 4" DEPTH)	4,761	CUBIC YARD		
31	TOP SOIL (1,100 FT <sup>2</sup> @ 6" DEPTH - PLANTER BED NORTH EAST)	21	CUBIC YARD		
32	KENTUCKY BLUE GRASS BLEND SEED MIX	389,500	SQUARE FOOT		
33	WEED BARRIER FABRIC	1,255	SQUARE FOOT		
34	SHREDDED BARK MULCH 1,100FT <sup>2</sup> @ 4" DEPTH-PLANTER BED NORHT EAST)	14	CUBIC YARD		
35	2" CALIPER TREE (EXACT PLACEMENT TO BE COORDINATED WITH CITY PM)	64	EACH		
36	5 GALLON SHRUB	12	EACH		
37	1 GALLON SHRUB	9	EACH		
38	IRRIGATION FOR TURF SOD & PLANTER BEDS	390,600	SQUARE FOOT		
SUB TOTAL					\$ -

**NOTE:** The quantities within this Bid Schedule are provided as a convenience for the bidder to aid in the bidding process. It will be the responsibility of each bidder to verify all quantities and provide all prices respectively. If additional items are identified beyond what is provided within this bid schedule, the bidder shall provide information and pricing for the item or items as part of their bid. The items will be reviewed by PEC and approved by the City. Any approved items will be added as an addendum accordingly.

**BASE BID (SOUTH SITE) TOTAL** \$ -

**Purchased by City and Installed by Contractor**

**(NIC) Purchased and Installed by City**  
 (SUPPLY & INSTALL CONDUIT AS REQUIRED.)

<b>ALTERNATE BID ITEM 2.0 - TURF SOD INSTEAD OF SEED</b>					
A.2.0	TURF SOD (PROVIDE DIFFERENTIAL INSTALL UNIT PRICE FOR TURF SOD INSTEAD OF GRASS SEED AS PER LINE ITEM 34 - (E.G., .52 CENTS FOR SOD LESS .12 CENTS FOR SEED = .40 CENTS/FT <sup>2</sup> ))	398,720	SQUARE FOOT		
SUB TOTAL					\$ -

<b>ALTERNATIVE BID ITEM 3.0 - ANGLED PARKING ALONG 500 EAST (35 STALLS)</b>					
A.3.0	REMOVE EXISTING CURB & GUTTER, SIDEWALK, & LANDSCAPE ALONG 500 E. ADD NEW STORM DRAIN SYSTEM. CORRELATE NEWLY PROPOSED CURB & GUTTER, SIDEWALK AND LANDSCAPE FOR ANGLED PARKING ALONG 500 East PER RELATED BID ITEMS BELOW.	1	LUMP		
A.3.1	24" CURB & GUTTER (INCLUDES 6" UNTREATED BASE COURSE)	560	LINEAR FOOT		
A.3.2	ASPHALT PAVING (6,515 FT <sup>2</sup> @ 3" DEPTH)	115	TON		
A.3.3	UTBC (6,515 FT <sup>2</sup> @ 6" DEPTH) - PARKING	230	TON		
A.3.4	PARKING STALL STRIPING (35 STALLS + 1 @ 20' LONG)	720	LINEAR FOOT		
A.3.5	48" WIDE CONCRETE WATERWAY	2,000	SQUARE FOOT		
A.3.6	CONCRETE SIDEWALK (10' WIDE)	5,435	SQUARE FOOT		
A.3.7	UTBC (6" DEPTH OVER 18,085 FT <sup>2</sup> ) - SIDEWALK	138	TON		
A.3.8	TOP SOIL (1,740 FT <sup>2</sup> @ 6" DEPTH - PLANTER BEDS)	33	CUBIC YARD		
A.3.9	WEED BARRIER FABRIC	1,740	SQUARE FOOT		
A.3.10	BARK MULCH (1,740FT <sup>2</sup> @ 4" DEPTH)	22	CUBIC YARD		
A.3.11	2" CALIPER TREE	5	EACH		
A.3.12	5 GALLON SHRUB	15	EACH		
A.3.13	1 GALLON SHRUB	30	EACH		
A.3.14	IRRIGATION	1,800	SQUARE FOOT		
SUB TOTAL					\$ -

**COMBINED ALT. BID TOTALS** \$ -